



End-of-Line Testing Specification for BESS Pack Assembly Lines

Applications: Utility-scale BESS pack lines, C&I energy storage, containerized battery systems
Target audience: Production engineers, quality managers, procurement teams specifying EOL test stations

1. Introduction

A BESS pack that passes EOL testing is not necessarily a good pack—but a BESS pack that fails EOL testing is guaranteed to be a bad one. For manufacturers shipping 280Ah or 314Ah LFP packs into utility-scale projects, the EOL testing station is the last gate before a multi-million-dollar liability leaves the factory floor.

This application note defines the minimum EOL test sequence, acceptance thresholds, equipment specifications, and takt time considerations for BESS prismatic pack assembly lines. The content is derived from 30+ commissioned ESS lines producing packs ranging from 50 kWh C&I units to 400 kWh containerized BESS systems, deployed between 2023 and 2026.

2. The Six Mandatory EOL Tests

Every BESS pack must pass all six tests below before release. Skipping any test to save cycle time is the most common cause of field returns in the first 12 months of a new line.

#	Test	Purpose	Typical Duration
1	Open Circuit Voltage (OCV)	Verify cell voltage balance within module	10–15 s
2	Insulation Resistance	Confirm dielectric isolation between busbar network and pack enclosure	15–30 s
3	Hi-Pot (Dielectric Withstand)	Stress insulation at elevated voltage to detect latent defects	20–60 s
4	Internal Resistance (DCIR)	Identify high-resistance joints from welding or bolting defects	10–20 s
5	BMS Communication	Verify CAN/RS485 handshake, cell-level data acquisition, protection circuit response	30–60 s
6	Air Tightness (Helium or Pressure Decay)	Confirm pack enclosure sealing for IP67/IP65 rated outdoor BESS	60–180 s

FIELD DATA

Lines that omit air tightness testing report 3–5x higher field return rates for water ingress within the first 18 months of deployment, particularly in coastal and tropical installations.

3. Acceptance Thresholds by Pack Type

The thresholds below apply to standard 280Ah / 314Ah LFP prismatic BESS packs. Projects with custom cell formats or extreme environment requirements should adjust in consultation with the cell manufacturer's specification sheet.

Test	Standard BESS (Indoor C&I)	Utility-Scale (Outdoor Container)	Instrument Accuracy
OCV	Cell-to-cell $\Delta V \leq 20$ mV within module	Cell-to-cell $\Delta V \leq 10$ mV within module	± 1 mV
Insulation Resistance	≥ 500 M Ω at 500 V DC	≥ 1000 M Ω at 1000 V DC	$\pm 2\%$ reading
Hi-Pot	1500 V AC for 60 s, leakage ≤ 5 mA	2500 V AC for 60 s, leakage ≤ 5 mA	$\pm 1\%$ voltage, ± 0.1 mA current
DCIR	Module-level ≤ 0.5 m Ω above cell spec	Module-level ≤ 0.3 m Ω above cell spec	± 0.01 m Ω
BMS Communication	CAN 2.0B handshake, all cell voltages readable, temperature sensors within ± 2 $^{\circ}\text{C}$	Same + RS485 daisy-chain verification, protection circuit activation test	Protocol analyzer required
Air Tightness	Pressure decay: 500 Pa drop ≤ 50 Pa in 60 s	Helium sniff: leak rate $\leq 1 \times 10^{-6}$ Pa $\cdot\text{m}^3/\text{s}$	Calibrated to NIST-traceable standard

CRITICAL NOTE

Hi-Pot test voltage must be selected based on the pack's maximum working voltage, not the cell nominal voltage. A 1500 V pack requires 2500 V AC Hi-Pot per IEC 62619. Using 500 V on a 1500 V pack provides no meaningful insulation validation.

4. Takt Time Calculation for EOL Stations

The EOL testing station is the most common bottleneck on BESS pack lines. A miscalculated takt time here reduces the entire line's OEE by 15–25%.

Equation: EOL Station Takt Time

$$T_{\text{EOL}} = \Sigma(\text{test durations}) + \text{handling time} + \text{pass/fail decision time}$$
$$T_{\text{EOL}} = (15 + 30 + 60 + 20 + 60 + 120) + 30 + 10 = 345 \text{ s} \approx 5.75 \text{ min}$$

For a line targeting 5 PACK/hr (720 s takt), a single EOL station at 345 s is not a bottleneck. But for a 10 PACK/hr line (360 s takt), a single station cannot keep up. Solutions:

Strategy	Throughput Gain	Cost Impact
Parallel dual EOL stations	2x capacity	+40% EOL equipment cost
Split sequence: electrical + mechanical in separate stations	1.5x capacity	+25% floor space
Skip air tightness for indoor C&I packs	Save 120–180 s	Not recommended for outdoor
Reduce Hi-Pot duration from 60 s to 30 s	Save 30 s	Acceptable if validated with 500-sample Cpk study

5. Equipment Selection Criteria

5.1 OCV / DCIR Tester

Parameter	Specification
Measurement range	0–5 V DC (OCV), 0–5 mΩ (DCIR)
Accuracy	OCV ±1 mV, DCIR ±0.01 mΩ
Probe type	Spring-loaded Kelvin (4-wire) probes, gold-plated
Channels	Multi-channel for simultaneous module-level scan (min 24ch)
Integration	MES data upload via Ethernet/IP or Modbus TCP

5.2 Hi-Pot / Insulation Tester

Parameter	Specification
Output voltage	0–5000 V AC, programmable
Leakage measurement	0–20 mA, resolution 0.01 mA
Dwell time	1–999 s programmable
Safety interlock	Dual-channel safety relay, PL d per ISO 13849
Discharge circuit	Automatic discharge to <50 V within 2 s of test completion

5.3 BMS Communication Test Station

Parameter	Specification
Protocols	CAN 2.0B, RS485, Modbus RTU
Test sequence	Handshake → cell voltage readout → temperature readout → protection circuit activation → fault injection response
Fault injection	Over-voltage, under-voltage, over-temperature simulation via software
Data logging	All cell voltages, temperatures, and fault responses logged to MES

5.4 Air Tightness Tester

Parameter	Pressure Decay Method	Helium Method
Sensitivity	~50 Pa resolution	1×10 ⁻⁷ Pa·m ³ /s
Test time	60–180 s	30–120 s

Parameter	Pressure Decay Method	Helium Method
Equipment cost	\$8,000–15,000	\$40,000–80,000
Recommended for	Indoor C&I packs (IP54)	Outdoor utility-scale (IP67)

SELECTION GUIDE

For packs destined for outdoor containerized BESS with IP67 rating, helium leak testing is strongly recommended. Pressure decay cannot reliably detect seal pinhole leaks below 0.5 mm diameter—exactly the defect size that causes moisture ingress over a 10-year service life.

6. Design Example: 1 GWh BESS Line EOL Configuration

Project: Southeast Asian utility-scale BESS factory, 1 GWh/year, 280Ah LFP, 1P16S module → 52-module rack, outdoor containerized deployment.

EOL station configuration:

Station	Tests	Duration	Equipment
Station 1 (Electrical)	OCV + DCIR + Insulation + Hi-Pot	125 s	Hioki BT3562 + custom Hi-Pot
Station 2 (Functional)	BMS comm + protection circuit	60 s	CAN analyzer + fault injection box
Station 3 (Sealing)	Helium leak test	90 s	INFICON ECOTEC E3000
Total	6 tests	275 s + 30 s handling = 305 s	

Results after 6 months of production:

Metric	Result
Pack first-pass yield	99.4%
EOL station OEE	91%
Field return rate (12 mo)	0.02%
Line bottleneck	Helium test (mitigated by parallel station)

KEY DECISION

The initial design used pressure decay for sealing test. After 3 moisture-ingress field returns in the first 2 months, the station was upgraded to helium leak testing. Zero sealing-related returns in the subsequent 4 months.

7. EOL Test Station RFQ Checklist

Specification Items

- ☐ Pack dimensions and weight range defined
- ☐ Pack voltage class (LV/HV) and max working voltage stated
- ☐ Required test items listed with pass/fail thresholds
- ☐ Takt time target per station stated
- ☐ Fixture design accommodates all pack variants
- ☐ MES data format and protocol specified

Vendor Evaluation

- ☐ Instrument brand and model disclosed (not "equivalent")
- ☐ Calibration certificates provided for all instruments
- ☐ Safety interlock architecture documented (PL level)
- ☐ FAT test plan includes 8-hour continuous run
- ☐ Spare parts list with lead times provided
- ☐ Remote support capability (VPN/teamviewer) confirmed

☐ Instrument calibration plan included

☐ Reference sites with similar pack format available

8. Common EOL Testing Mistakes

Mistake	Consequence	Correct Approach
Using 500 V Hi-Pot on 1500 V pack	Latent insulation defects pass EOL, fail in field after 6–12 months	Hi-Pot voltage = 1.67× max working voltage per IEC 62619
Skip BMS protection circuit test	Protection board DOA not detected until field commissioning	Always inject over-voltage/over-temp fault and verify BMS response
Pressure decay for outdoor IP67 pack	Pinhole leaks undetected, moisture ingress in humid climates	Use helium leak testing for all outdoor-rated packs
No MES data binding for EOL results	No traceability for field returns, cannot identify root cause	Every test result logged with pack serial number and timestamp
Single EOL station for 10+ PACK/hr line	EOL becomes bottleneck, line OEE drops to 60–70%	Plan parallel or split stations from day one

About Huiyao Laser

Huiyao Laser Technology (Luoyang) Co., Ltd. is a manufacturer of battery module and PACK assembly lines, laser welding systems, and EOL testing equipment for EV and energy storage manufacturing. Our application engineering team provides on-site EOL station commissioning and test parameter validation for customer-specific pack configurations.

hy@huiyaolaser.com | www.huiyaolaser.com/contact.html | [EOL Testing RFQ Guide](#)

DOCUMENT VERSION HISTORY

Rev.	Date	Author	Changes
A	2026-08-14	Application Engineering Team	Initial release. Content derived from EOL testing blog articles (W15, W17, W24) and 30+ commissioned ESS line data (2023–2026).

Production Log: Source: HTML → PDF via Playwright (Chromium headless). Template: HY-AN-002 Rev. A. Content derived from blog articles *battery-pack-eol-testing-equipment-configuration-2026*, *battery-pack-eol-testing-equipment-rfq-specification-guide*, and *battery-pack-line-rfq-evaluation-scoring-framework-2026*. Reviewed by: Application Engineering Team. Next scheduled review: 2027-08 or upon new IEC standard revision.